OFFICE OF THE ASSISTANT ENGINEER, HEAD-QUARTER RANGE, MYSORE.

Abstract Notification, dated 24th August 1936.

The attention of the public is invited to the detailed notification calling for tenders for constructing Workmen's Quarters attached to the Sandal Oil Factory, Mysore, appearing on pages 1328-1330 in Part VI of the *Mysore Gazette*, dated the 27th August 1936. The earnest money to be deposited is Rs. 230 and the latest date for receiving tenders is 12 Noon of 7th September 1936.

S. RAMASWAMY,
Assistant Engineer.

HASSAN DIVISION.

Notification dated 24th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 2 P.M. on 22nd September 1936, for Restoring Rajagiri Voddu Register No. 589 of Belur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Rajagiri Voddu Register No. 589 of Belur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Rajagiri Voddu Reg. No. 589 of Belur Taluk.

Item No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
	BUND.				
1	Clearing jungle, removing roots and ant hills and cutting grips in old bund and refilling with watering and consolidation ..	Grade	4 0 0	25	
2	Earthwork to bund including watering and consolidation	C.yd.	0 5 0	4,551	

Item No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
3	Earthwork to bund using earth available from draft and approach clearing of the weir ..	C.yd.	0 1 9	1,912	
4	Rough stone revetment work	C.yd.	1 14 0	89	
5	Turfing the slopes of bund	S.yd.	0 0 11	5,291	
6	Providing and fixing new grade stones including cutting numbers and painting	Each	2 0 0	26	
7	Providing and fixing Reg. No. stone	,,	4 0 0	1	
8	Do do B. M. Stones ..	,,	3 0 0	6	
9	Do do Index Stone ..	,,	0 12 0	26	
	SLUICE				
1	Cut opening the bund and refilling, including watering and tamping	C.yd.	0 3 0	130	
2	Earthwork excavation in G. S.	,,	0 4 0	20	
3	Laying concrete in surki mortar	C.ft.	0 4 6	361	
4	Size Stone in surki mortar	,,	0 6 0	462	
5	Burnt stone slabs 6" thick, dressed and fixed, including cement pointing	S.ft.	0 10 0	131	
6	Pointing with cement mortar	L. S. Rs.	..	..	
7	Cutting grooves in slabs	Each	1 0 0	3	
8	Providing plug and rod	Each	10 0 0	1	
9	Fixing C. I. pipe of 7" diameter including carting (Pipes supplied Departmentally)	R.ft.	2 8 0	36	
10	Boiling water during execution	L. S. Rs.			
	WEIR LEFT.				
1	Draft and approach clearing excavation in ordinary soil	C.yd.	0 3 3	2,267	
2	Laying concrete in surki mortar	C.ft.	0 4 6	539	
3	Size stone in surki mortar	,,	0 6 0	1,071	
4	Laying cement concrete slabs for coping ..	C.ft.	1 0 0	102	
5	Building size stone dug for binding walls ..	C.yd.	4 0 0	109	
6	Building rough stone revetment for apron wings wherever necessary out of available stones ..	C.yd.	2 0 0	50	
7	Pointing with cement mortar, to the exposed faces of masonry	L. S. Rs.	..	..	
8	Putting jack bund to join with high ground with excavation	C.yd.	0 2 6	544	
1	Clearing approaches in the eight waste weir ..	L. S. Rs.			

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 21st August 1936.

The attention of the public is invited to notification calling for tenders for constructing a Dispensary at Belagur, Hosadurga Taluk, Chitaldrug District, published in pages 1331-1333, Part VI of the *Mysore Gazette*, dated 27th August 1936.

R. TIPPAIYA,
Executive Engineer.